

Year 24 of the Durable, Well-Constructed **HUSKY SHEDS!**



20 months ago, our program lost our shop and compound to a devastating fire. We will move in to the rebuilt facility in late August. The Sheldon High School Building Trades Program is again constructing 12 storage sheds in our stadium parking lot this fall. These sheds are less expensive than commercially built sheds, and are built with superior materials and workmanship. Even though the cost of materials has sharply risen in recent years, we continue to hold our prices steady.

Standard features include:

- Pressure-treated 4x6 floor girders supporting 2x6 joists on 16" centers
- 3/4" tongue and groove painted plywood flooring
- 2x4 wall studs on 16" centers
- 30 year composition roof with drip flashing
- 5/8" T-111 pre-primed Doug Fir siding
- Gradual 3/12 roof pitch with 2x6 rafters
- Stanley steel clad door with deadbolt and door lock OR 6' wide roll up door (see picture above)
- Multiple screened vents and 30 year caulking
- 8" rafter overhang capped with 2x6 barge rafter

Payment plan includes 50% down, and a periodic payment plan with balance due upon completion.

Prices:

- (4) 8 x 12 \$4000
- (8) 10 x 12 \$4500

Delivery is available for \$350

For more information, contact instructor Jeff Merker at jmerker@egusd.net or (916) 947-4902